

# KUPERBERG DREAMS

STEVEN HURDER AND ANA RECHTMAN

## 1. BIRTH OF A METHOD

In August 1993, Krystyna Kuperberg wrote out a 3 page sketch, of a construction of what she thought would be a  $C^3$ -counterexample to the Seifert Conjecture. The idea for this construction had occurred to her earlier in the month, while attending the *Georgia Topology Conference* in Athens, Georgia. She faxed these notes to her son Greg, with the admonition that he wait for a more final draft. In the following days, she wrote out the precise construction, which expanded to an 8 page note, and realized that it was a  $C^\infty$ -counterexample. Greg then sent an email to several leading topologists, announcing the exciting news, that his mother had found a smooth counterexample to the Seifert Conjecture!

The announcement of Krystyna's work caused a sensation. William Thurston lectured on her construction at the MSRI, Berkeley in September, and observed that the construction could be realized as a *real analytic* aperiodic flow. Krystyna mailed around 60 copies of the manuscript to mathematicians around the world. Then in October, she gave a plenary lecture on her work at the conference in honor of Morris Hirsch in Berkeley California. Elsewhere, a seminar was held in Tokyo in November, as part of the *International Symposium/Workshop: Geometric Study of Foliations*. The participants in this informal seminar included, among many others, Shigenori Matsumoto, Étienne Ghys, Paul Schweitzer, and the first author.

The manuscript by Kuperberg was published almost immediately in the **Annals of Mathematics** [27]. Moreover, soon afterwards, Ghys presented Kuperberg's work in a Séminaire Bourbaki [10] in June 1994. Matsumoto wrote a report in Japanese [35], also in 1994, which provided more results about the dynamical properties of these "Kuperberg flows", with detailed proofs of their properties. The joint paper by Greg and Krystyna [28] contained many new ideas and variations on the basic construction. The brief note [31] gives an overview of Krystyna's work on aperiodic flows. Finally, Krystyna Kuperberg [30] gave a report to the *International Congress of Mathematicians* in 1998.

Krystyna commented on her work: "once you see the construction, you see it". In addition, her original sketches of the construction, involving a thickened annulus with "rabbit ears", were replaced in the published version by the now very familiar images drawn by her husband, Włodzimierz (Włodek), which conveyed a strong intuitive feel for the construction. Krystyna Kuperberg was a student of Karol Borsuk in Warsaw, and many of her works correspondingly use a strong geometric approach to analyzing problems in dynamical systems, and this is more than true for her construction of the Seifert counter-examples.

The goals of this essay are to discuss the antecedents to the Kuperberg construction, and give some inkling of the ideas that led Krystyna to her construction. In addition, we speculate on extensions of the construction and its future, especially in the context of other aspects of the theory of smooth dynamical systems. First, in Section 2 we recall the radical idea that made the Kuperberg construction possible, as it was a break from the past approaches to constructing counterexamples in a crucial manner. Section 3 gives a concise overview of known results about the Kuperberg flow. We then discuss in Section 4 questions about alternate flow dynamics for non-generic constructions of Kuperberg flows. Section 5 discusses speculations and open problems for flows that preserve some additional geometric structure.

---

Preprint date: November 30, 2021.

2020 *Mathematics Subject Classification*. Primary 37-03, 37C10, 37C70, 37B45.

## 2. SHAPE OF PLUGS

In his 1950 work [45], Seifert introduced an invariant for deformations of non-singular flows with a closed orbit on a 3-manifold, which he used to show that every sufficiently small deformation of the Hopf flow on the 3-sphere  $\mathbb{S}^3$  must have a closed orbit. He also remarked in Section 5 of this work:

*It is unknown if every continuous (non-singular) vector field on the three-dimensional sphere contains a closed integral curve.*

This remark became the basis for what is known as the ‘‘Seifert Conjecture’’:

*Every non-singular vector field on the 3-sphere  $\mathbb{S}^3$  has a periodic orbit.*

There must exist at least one minimal set for a flow on a compact manifold - a closed invariant subset which is minimal for this property. A periodic orbit is a minimal set, but if there are no periodic orbits for a flow, then a minimal set for the flow will have a possibly far more complicated topology. So one can ask if there are restrictions on the *shape* of a minimal set for an aperiodic flow? Karol Borsuk defined the shape of a topological space as an inverse limit continuum defined by a sequence of ANR approximations of the space [2, 3, 33, 34]. For an aperiodic flow on a 3-manifold, it seems that the minimal set must have a complicated shape, though just how complicated is an open question.

Kuperberg’s strategy for the construction of an aperiodic flow was not based on the choice of an invariant minimal set with prescribed shape, but was instead to create a dynamical framework which avoided the implications of the Brouwer Fixed-Point Theorem. We explain this remark in the following discussions.

The first general approach to the Seifert Conjecture was made in the 1966 paper by Wesley Wilson [49], where he showed that every closed 3-manifold  $M$  has a flow with only finitely many closed orbits. Wilson introduced the use of a special kind of ‘‘plug’’ to modify a given flow, and this idea profoundly influenced the thinking about the constructions of flows with special properties, and the Seifert conjecture in particular.

A *Wilson plug* for a flow on the 3-manifold  $M$  is a neighborhood  $P \subset M$  diffeomorphic to **an annulus** cross an interval,  $P \cong \mathbb{A}^2 \times [-1, 1]$ , where orbits enter one end of the plug,  $\partial^- P = \mathbb{A}^2 \times \{-1\}$ , and exit the other end,  $\partial^+ P = \mathbb{A}^2 \times \{+1\}$ . The key idea introduced by Wilson was that the plug flow should be symmetric: an orbit which traverses the plug should enter and exit at symmetric points on the faces. No such restriction is placed on an orbit which enters the plug and never exits, of course, and one assumes there are such orbits. Wilson introduced the technique of using a plug reflected on itself to achieve this symmetry property. As a result, the plugs he uses have two periodic orbits, as illustrated in Figure 1.

A plug can be inserted into any non-singular flow on a manifold, not just once but any finitely number of times as needed, to modify a given non-singular flow. Wilson showed that any flow can be modified using finitely many plugs to obtain a flow with only isolated periodic orbits. It is an observation in [40] that by appropriately arranging the insertion of Wilson plugs, one can obtain a flow with exactly two periodic orbits.




FIGURE 1. An example of a Wilson plug with two periodic orbits

Subsequently, in the early 1970's, Paul Schweitzer had the inspired idea to construct a modified Wilson-type plug, but instead of the top and bottom boundaries of the plug being annuli, they were diffeomorphic to a 2-torus with an open disk removed, as illustrated in Figure 2. The paradigm shift of a Schweitzer plug is that the faces of the plug are immersed in the transverse space, but still transverse to the flow. Using a plug with this shape, the second key point was to double the construction using a mirror symmetry as with the Wilson plug, so that the flow in the plug has two Denjoy-type minimal sets, instead of two circles.

A Denjoy minimal set, as introduced by Denjoy in [8], has the shape of a wedge of two circles. The Schweitzer plug has the celebrated “double doughnut” shape as seen in Figure 2. This plug can then be inserted into flows on 3-manifolds to create new flows which have all minimal sets of Denjoy type. In particular, using this plug one can construct flows with no periodic orbits. Thus, Schweitzer showed that every 3-manifold carries a  $C^1$ -flow with no periodic orbits! This celebrated result appeared in the **Annals of Mathematics** [43], and in his talk [44] to the *International Congress of Mathematicians* in 1974.




FIGURE 2. The Schweitzer plug

Mike Handel showed in his 1980 paper in the **Annals of Mathematics** [12] a result which severely limits the shape of a minimal set for a smooth aperiodic flow – it cannot be embedded as the minimal set for a flow on a surface. Thus, a flow with a “Denjoy type” minimal set carried by a surface cannot be  $C^2$ . This was an attempt to prove that plugs were not the method to find smooth aperiodic flows on  $\mathbb{S}^3$ .

Jenny Harrison showed in [13] that the Schweitzer plug could be modified to obtain an aperiodic plug with a  $C^{2+\delta}$ -regular flow, by embedding the Denjoy minimal sets in a “3-dimensional” fashion. However, this result required delicate arguments, and obtaining any further improvement in the differentiability of the flow using this method, seemed completely out of reach. The Handel and Harrison works suggested that any counter-example to the Seifert Conjecture was going to require a radically new approach.

Meanwhile, in 1979, the Kuperbergs were attending the *Scottish Book Conference* in Denton, Texas, organized by Dan Mauldin [36]. At this conference, Stanislaw Ulam told Krystyna and Wlodek about an unsolved problem, posed by Ulam:

[36, Problem 110] *Let  $M$  be a manifold. Does there exist a numerical constant  $K$  such that every continuous mapping  $f: M \rightarrow M$  which satisfies the condition  $|f^n(x) - x| < K$  for  $n = 1, 2, \dots$  must possess a fixed point:  $f^n(x_0) = x_0$ ?*

The mathematician/inventor Coke Reed was a colleague of Ulam at Los Alamos, and later a colleague of Krystyna at Auburn University. Kuperberg and Reed discussed this problem, and subsequently solved it. They gave counter-examples to the assertion in Problem 110, as published in the 1981 work [24]. The methods they developed are analogous to the methods introduced by Wilson in [49]. Kuperberg and Reed improved their result in the 1989 paper [25] via an application of the Schweitzer plug. An analysis of the solutions to the Ulam Problem 110 were recalled and analyzed in the paper [26] by K. Kuperberg, W. Kuperberg, P. Minc and C. Reed. There is a connection between the solutions of the Ulam Problem and the construction of counter-examples to the Seifert Conjecture, in that the plug technique can be applied to construct counter-examples to both, as remarked in the joint work of Greg and Krystyna [28, Theorem 8].

Following the successful solution to the Ulam Problem 110, Kuperberg began to consider what was required to construct a smooth plug without periodic points for the flow. As she remarked [32], the problem was always the *Brouwer Fixed-Point Theorem*: any map of a (transverse) disk to itself must have a fixed point,

and so a corresponding suspension flow will have a periodic orbit. Thus, to build a flow in a plug without periodic orbits, the transverse holonomy for the flow must be a “translation” on an infinite line or region.

The inspired geometric observation is that such a translation is already available in the Wilson plug, as the flow on the Reeb cylinder, as pictured in Figure 3 below.




FIGURE 3. Reeb flow on cylinder

The flow of a point below the orbit  $\mathcal{O}_1$  will climb up to the periodic orbit  $\mathcal{O}_1$  and the return map of this flow is a translation on a vertical interval in the cylinder transverse to the flow. A similar dynamical behavior happens for points in the cylinder above the periodic orbit  $\mathcal{O}_2$ , but in reverse time.

With this point of view, one can then ask: how to get the flow of the periodic orbit to “break open” and “start climbing the holonomy staircase”? That is, break open the periodic orbit using its own holonomy! The solution is the second inspired idea behind Kuperberg’s construction, to insert the flow on the Wilson cylinder into itself, so that the orbit  $\mathcal{O}_1$  is inserted into one of the flow lines climbing up to  $\mathcal{O}_1$ . This is precisely what the insertion maps illustrated in Figure 5 below accomplish. To make this work and keep the plug properties, one must first do a “double twist” of the embedding of the Reeb cylinder, as illustrated in Figure 4 below. (See also the illustration on the left side of Figure 8.) According to Krystyna, the idea for doing this construction occurred to her during a beer party at the Georgia Topology Conference.





FIGURE 4. Embedding of Wilson Plug  $W$  as a *folded figure-eight*

The essence of the novel strategy behind the aperiodic property of the flow  $\Phi_t$  on a Kuperberg Plug is perhaps best described by a quote from the paper by Matsumoto [35]:

We therefore must demolish the two closed orbits in the Wilson Plug beforehand. But producing a new plug will take us back to the starting line. The idea of Kuperberg is to *let closed orbits demolish themselves*. We set up a trap within enemy lines and watch them settle their dispute while we take no active part.

The reader is extolled to read the proof that these flows are aperiodic in [27], or in the reports by Ghys [10] or Matsumoto [35], as the elegance of Kuperberg’s idea is revealed in the simplicity of this proof.

Note that there are many choices of the vector field that can be made for the flow in a Wilson plug. What is essential for Kuperberg’s construction is that there are the two closed orbits which attract/repel a set of orbits entering or leaving a face of the plug.

FIGURE 5. The Kuperberg Plug  $\mathbb{K}_\epsilon$ 

A Kuperberg plug can also be constructed for which its flow  $\mathcal{K}$  is real analytic. An explicit construction of such a flow is given in Section 6 of the paper [28] by Greg and Krystyna Kuperberg. There is the added difficulty that the insertion of the plug in an analytic manifold must also be analytic, which requires some subtlety. Analytic aperiodic flows are discussed in the second author's Ph.D. Thesis [41].

The construction of smooth aperiodic flows on compact manifolds using the Kuperberg method produces orbits that never close up, so they wander around a compact region of a plug that has been inserted. There is much that can be said about the dynamical properties of these flows, deduced from the way the flows in the plugs are constructed. These are the *known knowns* about Kuperberg flows, as discussed in Section 3.

There are also many *known unknowns* about Kuperberg flows, which generate interesting open questions about the dynamics of the Kuperberg flows, as discussed in Section 4. There are also the *unknown unknowns*, which are speculations of dynamical phenomena yet to be discovered for this class of smooth flows.

### 3. APERIODIC FLOW DYNAMICS

Ghys observed in [10] that a Kuperberg flow has zero topological entropy. This follows from the remark that for a smooth flow on a compact 3-manifold, Katok's results in [22] imply that if a smooth flow has positive entropy, then it must have periodic orbits. Thus, aperiodic flows belong to a class of smooth dynamical systems which might be considered "less than chaotic", or more precisely "at worst, slowly chaotic".

The flow in the Wilson plug in Figure 1 has two periodic orbits, labeled  $\mathcal{O}_1$  and  $\mathcal{O}_2$ . Both of these orbits are broken open by the insertion surgery illustrated in Figure 5, to yield what are called the *special orbits* for the flow. Not as obvious without a closer inspection, is that each of the special orbits is trapped inside of the Kuperberg plug formed by the surgery, and they limit on each other. Thus, their closures form a minimal set for the flow in the plug. Furthermore, every orbit entering the plug either escapes from the plug on the opposite face, or else it limits on the closure of a special orbit. Thus, there exists a unique minimal set for the flow in the plug. If the aperiodic flow is constructed using multiple Kuperberg plugs, then there may be multiple minimal sets, each disjoint from the other. For simplicity of exposition, we assume there is only one plug, and let  $\Sigma$  denote the unique minimal set.

Another highly non-obvious result due to Matsumoto [35, Proposition 7.2], see also the discussion in [10, Section 8], is that there is an open set of points in the entrance of a Kuperberg plug whose forward orbits limit on the minimal set  $\Sigma$ . As the minimal set  $\Sigma$  is contained in the interior of the plug, this open set consists of non-recurrent points for the flow. In particular, this implies that there is no invariant probability measure in the Lebesgue measure class, for the flow in the Kuperberg plug. It is remarked after the proof of [28, Proposition 18] that the Matsumoto argument works for  $C^1$ -flows, and some but not all piecewise-linear self-insertions [28, Section 9].

Remarkably, Greg Kuperberg showed in Theorem 1 of [29] that on every closed 3-manifold there is a volume-preserving  $C^1$ -vector field with no closed orbits, obtained by modifying the Schweitzer plug. He also proved in Theorem 2 of [29] that for every closed 3-manifold, there is a volume preserving  $C^\infty$ -flow with a finite

number of periodic orbits. Also in the volume preserving setting, Viktor L. Ginzburg and Başak Gürel [11], constructed a version of Schweitzer’s plug that allows to produce examples  $C^2$ -functions on symplectic 4-manifolds, having a level set whose Hamiltonian vector field has no periodic orbits. A Hamiltonian vector field always preserves volume and in this case is  $C^1$ , hence it gives examples of aperiodic volume preserving flows.

The final general remark about the geometry of the Kuperberg flows is more complicated to explain, but has profound consequences for their dynamics. The Reeb cylinder is an annular region bounded by the two periodic orbits for the Wilson flow, as pictured on the right side of Figure 1. The process of doing flow surgery as illustrated in Figure 5 cuts two “notches” out of the cylinder. This is the region labeled by  $\mathcal{R}'$  on the left side of Figure 6 below, called the “notched Reeb cylinder” as pictured on the right side of Figure 1, before the cylinder is deformed to appear as in Figure 4, which is then twisted as in Figure 5.




FIGURE 6. Notch and the flow of its boundary arc

The Kuperberg flow in the Wilson cylinder preserves the region  $\mathcal{R}'$ , called the *notched Reeb cylinder*, until it reaches a notch, then it continues to flow but the orbits are not longer in the cylinder, as in Figure 5. This produces a tongue-shaped region as illustrated on the right side of Figure 6. This tongue region continues to flow until it intersects the insertion regions created by the surgery, and the pattern repeats ad infinitum, attaching tongues to the tongues.

The complete flow of the *notched Reeb cylinder* is a surface with boundary embedded in the Kuperberg plug. Figure 7 gives three illustrations of this central object for Kuperberg flows, which Siebenmann called a “chou-fleur” in his communication [47]. This was illustrated by Ghys as a “fractal-like cluster” in [10], as pictured in the lower left side of Figure 7. In the monograph [15], the authors called the surface as laid out on the plane, a “propeller”, which is approximately illustrated by the thickened 2-dimensional, tree-like structure on the right side of Figure 7, but again not to scale (all the branches have approximately the same width). We call this infinite surface  $\mathfrak{M}_0$ .

The basic observation is that the boundary of  $\mathfrak{M}_0$  is the union of the special orbits for the flow! Thus, to understand the dynamics of the flow, one analyzes the structure of the propellers in the Kuperberg plug, which are defined by a recursion process that is generated by the insertion surgery. The recursion process which defines the branches of the propeller depends in a sensitive manner on the precise surgery process used to construct the plug. This makes the analysis very delicate, and more will be said about that later.

The Kuperberg flow preserves the embedded infinite surface  $\mathfrak{M}_0$ , whose boundary contains the special orbits. The fact that the flow is aperiodic corresponds to the fact that the propellers are infinite.

The closure  $\mathfrak{M} = \overline{\mathfrak{M}_0}$  is a type of 2-dimensional *lamination with boundary* that contains the minimal set  $\Sigma$ . Thus, the topological shape of the minimal set  $\Sigma$  is dominated by the shape of the lamination  $\mathfrak{M}$ , which can be estimated using the recursion on the reinsertions of the notched Reeb cylinder for the Kuperberg plug. This approach to the study of the shape of  $\Sigma$  is taken in [15]. Conversely, the inclusion  $\Sigma \subset \mathfrak{M}$  suggests possible relations between the shape of  $\mathfrak{M}$  and the dynamical properties of the flow, as discussed in Section 4.

We describe the technical setting for comparing  $\Sigma$  and  $\mathfrak{M}$ . The drawing on the left side of Figure 8 below gives an expanded view of the insertions illustrated in Figure 5. A key point is that the image of a boundary orbit, denoted by  $\tau(\mathcal{O}_1)$  in the illustration, has image under the insertion as a twisted curve that is tangent




FIGURE 7. The surface  $\mathfrak{M}_0$  - as Serpent, Chou-fleur, or Propeller

to the cylinder at the boundary curve  $\mathcal{O}_1$ , but intersects transversally  $\tau(\mathcal{O}_1)$ . This results in a picture as on the right side of Figure 8, where the two thickened curves are the boundaries of the cylinder and its insertion.

The graph on the right side of Figure 8 is called the *radius function* (actually, what is illustrated is the inverse of this function) and the “quadratic shape” of the graph is the basis for showing that the Kuperberg flow is aperiodic. Understanding these remarks takes some effort, and is explained in the papers [27, 10, 35, 15], but reveals the great beauty of the Kuperberg construction.

The authors introduced the notion of a *generic* Kuperberg flow in the work [15], which formulates a collection of optimal conditions on the choices for the construction of the flow. One of these conditions is that the radius function for the insertion is actually “quadratic”, as pictured on the right side of Figure 8. We show in [15] that for a generic Kuperberg flow, there is equality  $\Sigma = \mathfrak{M}$ , and thus one can study the shape of the minimal set for the flow by studying the properties of the 2-dimensional lamination with boundary  $\mathfrak{M}$ .




FIGURE 8. The image of  $L_1 \times [-2, 2]$  under  $\sigma_1$  and the radius function

#### 4. NON-GENERIC FLOWS

Ghys wrote in his 1995 survey [10, page 302]:

*Par ailleurs, on peut construire beaucoup de pièges de Kuperberg et il n'est pas clair qu'ils aient la même dynamique.*

In this section, we discuss some ways in which the dynamical properties of an aperiodic smooth Kuperberg plug vary with the choices made in its construction. The properties considered include the *shape* and the *Hausdorff dimension* of the minimal set  $\Sigma$ , and the *slow entropy* of the flow.

The construction of a Kuperberg flow begins with the choice of a flow  $\mathcal{W}$  on a cylinder, with an invariant cylinder bounded by the two periodic orbits that is called the *Reeb cylinder*, as illustrated on the left side of Figure 1. This flow is then extended smoothly to a thickened cylinder, or interval times an annulus, as on the right side of Figure 1. There are further symmetry conditions imposed on the flow  $\mathcal{W}$ , as given in [27, Section 3], or for example as specified by (P1) to (P4) in [15, Section 2]. The symmetry conditions still allow for a wide variation of choices for the flow  $\mathcal{W}$ .

The flow of the Kuperberg plug, that results from the insertion process, consists of orbit segments of the gradient like flow  $\mathcal{W}$  which are “patched together”. This view of the orbits, as a union of finite flows, is key to the analysis of the Kuperberg flow in the works of Ghys [10] and Matsumoto [35]. For a different take on this, Section 5 of the paper [28] describes the result of the self-insertion patching, as the analog of a “stacking subroutine” for a computer program. Then the fact that no orbit is periodic corresponds to showing that the routine does not terminate for the given starting point. So in essence, the solution to the Seifert Conjecture is realized by building a “dynamical computer program” that is non-terminating.

This patching of flow segments is occurring orbitwise, so if there is to be any hope of organizing this process in a unified description for the entire flow on the plug, one needs to impose assumptions on the flow  $\mathcal{W}$  that its orbits are as uniform as possible. Such additional conditions on  $\mathcal{W}$  are formulated in the works [27, 28], and even more restrictive conditions are imposed in [15].

The second step in the construction of a Kuperberg flow is to make a choice for each of the two insertion maps, as pictured in Figure 5 and Figure 8. In this step, the embedding of the Reeb cylinder makes a transverse contact at the periodic orbit, either the bottom or the top orbit, so as to break open these closed orbits. The result is that the special orbits which result by breaking open the closed orbits, they intersect the vertex of the parabola pictured on the right side of Figure 8. They return infinitely often to a neighborhood of the vertex of the parabola as a result of the translation holonomy of the flow. Hence, the germinal shape at its vertex of the parabolic map has a strong influence on the dynamics of the special orbit, and so on the dynamics of the entire flow.

A basic question is, when does the minimal set satisfy  $\Sigma = \mathfrak{M}$ ? Ghys gave a construction of a flow on a plug and sketched the proof that  $\Sigma = \mathfrak{M}$  for this flow, at the end of Section 7 in [10]. The Kuperbergs gave an explicit real analytic flow on a plug for which  $\Sigma = \mathfrak{M}$  in their joint paper [28]. In both cases, the idea of the proof is to show that the closure of a special orbit contains the notched Reeb cylinder  $\mathcal{R}'$ , hence contains the flow of  $\mathfrak{M}_0$  and thus equals its closure  $\mathfrak{M}$ .

The authors began our investigations of the shape of the minimal set in the Kuperberg flows in 2010, and for several years after that, every time we met Krystyna we had to admit we couldn’t answer one of the mysteries of the Kuperberg construction:

**PROBLEM 4.1.** *Is the minimal set always two dimensional for a smooth Kuperberg flow?*

This is the conclusion for the examples by Ghys in [10] and in the joint paper [28], but the situation in general was not known. In order to answer Krystyna’s question, we introduced the notion of a “generic Kuperberg flow” in [15], which assumes that the flow satisfies the conditions of Hypothesis 12.2 and Hypothesis 17.2 formulated in that work. Hypothesis 12.2 assumes in particular that the vertical component of the vector field  $\mathcal{W}$  on the Reeb cylinder has quadratic germ near the two periodic orbits at which its “vertical component” must vanish. This condition is used to show that the closure of the special orbits contain  $\mathcal{R}'$ . But it is unknown, for example, that if the vector field vanishes to higher order at the periodic orbits, can one still show that  $\mathcal{R}'$  is contained in the closure of a special orbit?

The equality  $\Sigma = \mathfrak{M}$  can be considered as a type of *Denjoy Theorem* for 2-dimensional laminations. The usual Denjoy Theorem states that the closure of an orbit for a  $C^2$ -flow without closed orbits on the 2-torus is all of  $\mathbb{T}^2$ . Then the equality  $\Sigma = \mathfrak{M}$  can be considered as analogous, for it states that the closure of an orbit is not a 1-dimensional submanifold of  $\mathfrak{M}$ , but fills up its 2-dimensional leaves. The known proofs



of this conclusion cited above, they all make assumptions on both the flow  $\mathcal{W}$  and on the insertion map. Formulating general criteria which suffice to imply the equality  $\Sigma = \mathfrak{M}$  has proven difficult.

If  $\Sigma \subset \mathfrak{M}$  is a proper inclusion, then the topological type of  $\Sigma$  and  $\mathfrak{M}$  will differ, for example they could have distinct shapes. A  $C^1$ -flow on  $\mathbb{T}^2$  without closed orbits provides a good model for this difference. If the minimal set  $\mathfrak{D}$  for the flow is not all of  $\mathbb{T}^2$  then  $\mathfrak{D}$  is a 1-dimensional continuum, as used in the construction of the Schweitzer plug. If  $p \in \mathbb{T}^2 - \mathfrak{D}$  then there is a retract of the open punctured torus  $\mathbb{T}^2 - \{p\}$  onto  $\mathfrak{D}$ , so that  $\mathfrak{D}$  has the shape of a wedge of two circles. It seems a very interesting problem to compare the shapes of the closed invariant sets for a general aperiodic flow:

**PROBLEM 4.2.** *Suppose the Kuperberg flow in a plug has minimal set  $\Sigma \subset \mathfrak{M}$  which is a proper inclusion. What is the relation between the shapes of  $\Sigma$  and  $\mathfrak{M}$ ?*

Theorem 19 in [28] gives the construction of aperiodic PL plugs for which  $\Sigma$  is 1-dimensional. In addition, there is a discussion of the symbolic dynamics for these special flows they construct. The consideration of the topological type of  $\Sigma$ , in addition to the known unknowns about its shape, one senses that its study leads into the realm of the unknown unknowns, that new dynamical phenomena will be discovered.

We next consider another dynamical aspect of Kuperberg flows, their entropy and the Hausdorff dimension of their minimal sets. While Ghys observed in [10] that an aperiodic flow must have entropy equal to zero, using a well-known deep result of Katok [22], none-the-less the dynamical behavior of the flow appears to be chaotic upon closer inspection.

The geometry of the propeller as pictured in Figure 7, suggests that the flow in the minimal set  $\Sigma$  should exhibit exponential behavior, as it follows the boundary of the propeller which appears to have exponentially growing area. This intuition is flawed, though, as the flow cannot simply travel down the core of the propeller, but must instead travel on the boundary to get to the extremities of the tree. The time required to get to the extremes of the tree is not linear, but grows approximately as the square of the distance to be traveled. This observation is the basis for Theorem 21.10 in [15]:

**THEOREM 4.3.** *The “slow entropy” of a generic Kuperberg flow is positive for exponent  $\alpha = 1/2$ .*

The notion of slow entropy was introduced by Katok and Thouvenot [23]. The exponent  $\alpha = 1/2$  is essentially saying that the entropy would be positive if the time variable is sped up by taking the square of time. We also note that for this result, the generic hypotheses include an extra condition, the assumption that the insertion maps for the construction of the plug have “slow growth” themselves. This is a technical property, but its requirement emphasizes that the proof of Theorem 4.3 is quite technically involved. In particular, the proof uses an estimate on the growth rates of leaves in the lamination  $\mathfrak{M}$ , that they grow at subexponential rate  $1/2$  as well. Define the growth rate of  $\mathfrak{M}$  as the exponential growth rate of the dense leaf  $\mathfrak{M}_0$ , so for a generic flow this rate is  $1/2$ . Also, define the entropy dimension  $HD(\mathfrak{M})$  of  $\mathfrak{M}$  as the least upper bound of the exponents  $0 \leq \alpha \leq 1$  such that the  $\alpha$ -slow entropy of the flow is positive [7]. Thus, for a generic flow we have  $HD(\mathfrak{M}) \geq 1/2$ . There are many questions one can ask about these invariants, for example:

**PROBLEM 4.4.** *What range of values for  $HD(\mathfrak{M})$  can be realized by aperiodic flows on 3-manifolds? Is there an aperiodic flow with  $HD(\mathfrak{M}) = 0$ ?*

For a Kuperberg flow, one can also ask about the Hausdorff dimension of the lamination  $\mathfrak{M}$ . This problem seems almost intractable, but Daniel Ingebreton developed an approach to calculating this dimension for a particular class of flows in his thesis work [20, 21].

**THEOREM 4.5.** [20] *The Hausdorff dimension of the minimal set for generic Kuperberg flow satisfies  $2 < d_h(\mathfrak{M}) < 3$ .*

The dimension of  $\mathfrak{M}$  must be at least 2, as  $\mathfrak{M}$  is a union of 2-dimensional “leaves” by the generic assumption. But the fact that the dimension is greater than 2 is a measure of the transverse complexity of  $\mathfrak{M}$ . The actual Hausdorff dimension appears to depend in a sensitive manner on the choices made. The thesis work also gives a method to numerically calculate this number. We can then formulate a question which falls into the category of an unknown unknown about Kuperberg flows:

**PROBLEM 4.6.** *Is there a relation between the slow entropy of a Kuperberg flow, and the Hausdorff dimension of its unique minimal set? Is there a relation if the flow is assumed to be generic?*

We should also mention a question that belongs to the class of “unknown unknown” problems.

**PROBLEM 4.7.** *How do the dynamics of a real analytic Kuperberg flow in a plug differ from the general smooth case? Are there further restrictions on the shape of the minimal sets in the analytic case?*

Another remarkable fact about the Kuperberg flows, is that they lie at the “boundary of chaos” in the  $C^\infty$ -topology on flows. The idea behind this remark is that when making the insertion as in Figure 8, one can stop the insertion “too soon”. That is, if the two cylinders do not make contact, then the insertion does not break open the periodic orbits for the Wilson flow  $\mathcal{W}$ . We show in [16] that the flow for such a truncated insertion again has two periodic orbits. However, the lengths of these orbits tends to infinity as the insertion limits to one which breaks open the orbits. Thus, we obtain smooth families of variations of the Kuperberg plug with simple dynamics, and exactly two periodic orbits, and the limit of the family is an aperiodic flow.

In such a family, the period of the periodic orbits must blow up at the limit. Palis and Shub in [38] asked whether this dynamical phenomenon can occur in families of smooth flows on closed manifolds, and called a closed orbit whose length “blows up” to infinity under deformation a “blue sky catastrophe”. The first examples of a family of flows with this property was found by Medvedev in [37]. The constructions in [16] show that deformations of Kuperberg flows provide a new class of examples. The work of A. Shilnikov, L. Shilnikov and D. Turaev in [46] further discusses “blue sky catastrophe” phenomenon.

On the other hand, when making the insertion as in Figure 8, one can take the insertion “too far”. That is, the two cylinders intersect not along one arc, *but along two arcs*. We show in [16] that the flow for these over-extended insertions have countably many embedded horseshoes, so an abundance of hyperbolic behavior. Moreover, as the insertion maps are deformed to one that just makes contact at a single point, then these horseshoes increase in number. The dynamics of the generic Kuperberg flow is thus the limit of the dynamical chaos in a continuous family of horseshoes for neighboring smooth flows.

The immediate conclusion is that the Kuperberg flows are not stable in the  $C^\infty$ -topology on flows.

The recitation of remarkable properties of the class of flows created by Kuperberg could continue, as they are zero entropy dynamical systems, which are simply not boring [17]! Instead, we want to also discuss a variety of other constructions and results following from Seifert’s Conjecture, and the questions they engender.

## 5. DECORATED FLOWS

As explained by Ghys [10], the construction of non-singular aperiodic flows is particularly complicated in dimension 3. The Seifert conjecture, that is false in full generality, can be decorated with invariant structures: we can ask, if the flow preserves something, then must it have a periodic orbit? On one hand, there are families of non-singular flows that always have periodic orbits, on the other hand we have the examples discussed previously in this text. Here we discuss this broader subject of flows on closed 3-manifolds, we review some results on the existence of periodic orbits. We do not intend to make an exhaustive list.

Let us start with the class of Reeb vector fields associated to a contact form. It has been shown by Hofer in [14], that the flow of a Reeb vector field on  $\mathbb{S}^3$  must have a periodic orbit, and this was generalized to every closed 3-manifold by Taubes in [48]. But we know more, in fact every Reeb vector field on a closed 3-manifold has at least two periodic orbits as proved by Cristofaro-Gardiner and Hutchings [6] and the examples with exactly two periodic orbits are completely understood [5]. The second author, together with Colin and Dehornoy, proved that if a Reeb field is non-degenerate then it has either two or infinitely many periodic orbits [4].

A Reeb vector field always preserves a volume form. A big open question in the subject, is whether a  $C^\infty$  volume preserving flow on a 3-manifold has a periodic orbit. It seems impossible to mimic Krystyna’s construction of a plug in this setting, but we can do a Wilson plug for volume preserving flows. The lack of examples of possible minimal sets, makes it also impossible to mimic other plug constructions.

In the case of Reeb flows, Alves and Pirnapasov [1] proved recently the existence of some knots such that if a Reeb flow has a periodic orbit realizing the knot then it has positive entropy. In particular, by the already mentioned theorem of Katok [22], such Reeb flows have lots of periodic orbits. It is an observation that such a result cannot hold for categories of flows for which we can construct plugs. Using a suitable Wilson plug one can prove the following:

**THEOREM 5.1.** *Let  $K$  be a given knot. Every 3-manifold that admits a zero entropy flow without fixed points, admits a zero entropy flow without fixed points having (at least) two periodic orbits whose knot type is  $K$ . Moreover, if the original flow is generated by a Reeb vector field, then the new flow preserves a plane field that fails to be a contact structure along the two periodic orbits of knot type  $K$ .*

The existence of periodic orbits was extended to geodesible volume preserving flows (also known as Reeb vector fields of stable Hamiltonian structures) on manifolds that are not torus bundles over the circle by Hutchings and Taubes [18, 19], and Rechtman [42], and for real analytic geodesible flows by Rechtman [42]. The existence of a periodic orbit is also established for real analytic solutions of the Euler equation by Etnyre and Ghrist [9]. Geodesible volume preserving flows are solutions to the Euler equation, but we do not know if the last ones have periodic orbits. We do know that it is impossible to construct plugs whose flow satisfies the Euler equation [39].

## REFERENCES

- [1] M. Alves and A. Pirnapasov, *Reeb orbits that force topological entropy*, Ergodic Theory and Dynamical Systems, 2021.
- [2] K. Borsuk, *Concerning homotopy properties of compacta*, **Fund. Math.**, 62:223–254, 1968.
- [3] K. Borsuk, **Theory of shape**, Monografie Mat., vol. 59, Polish Science Publ., Warszawa, 1975.
- [4] V. Colin, P. Dehornoy and A. Rechtman, *On the existence of supporting broken book decompositions for contact forms in dimension 3*, arXiv:2001.01448.
- [5] D. Cristofaro-Gardiner, U. Hryniewicz, M. Hutchings and H. Liu, *Contact three-manifolds with exactly two simple Reeb orbits*, arXiv:2102.04970.
- [6] D. Cristofaro-Gardiner and M. Hutchings, *From one Reeb orbit to two*, **J. Differential Geom.** 102, no. 1, 25–36, 2016.
- [7] A. de Carvalho, *Entropy dimension of dynamical systems*, **Portugal. Math.**, 54:19–40, 1997.
- [8] A. Denjoy, *Sur les courbes définies par les équations différentielles à la surface du tore.*, **J. Math. Pure Appl.**, 11:333–375, 1932.
- [9] J. Etnyre and R. Ghrist, *Contact topology and hydrodynamics. I. Beltrami fields and the Seifert conjecture*, **Nonlinearity**, 13:441–458, 2000.
- [10] É Ghys, *Construction de champs de vecteurs sans orbite périodique (d’après Krystyna Kuperberg)*, Séminaire Bourbaki, Vol. 1993/94, Exp. No. 785, **Astérisque**, Vol. 227: 283–307, 1995.
- [11] V.L. Ginzburg and B.Z. Gürel, *A  $C^2$ -smooth counterexample to the Hamiltonian Seifert conjecture in  $\mathbb{R}^4$* , **Ann. of Math. (2)**, 158:953–976, 2003.
- [12] M. Handel, *One-dimensional minimal sets and the Seifert conjecture*, **Ann. of Math. (2)**, 111:35–66, 1980.
- [13] J.C. Harrison,  *$C^2$  counterexamples to the Seifert conjecture*, **Topology**, 27:249–278, 1988.
- [14] H. Hofer, *Pseudoholomorphic curves in symplectizations with applications to the Weinstein conjecture in dimension three*, **Invent. Math.**, 114:515–563, 1993.
- [15] S. Hurder and A. Rechtman, *The dynamics of generic Kuperberg flows*, **Astérisque**, Vol. 377:1–250, 2016.
- [16] S. Hurder and A. Rechtman, *Aperiodicity at the boundary of chaos*, **Ergodic Theory Dyn. Systems**, 38:2683–2728, 2018.
- [17] S. Hurder and A. Rechtman, *Perspectives on Kuperberg flows*, **Topology Proc.**, 51:197–244, 2018.
- [18] M. Hutchings and C. Taubes, *The Weinstein conjecture for stable Hamiltonian structures*, **Geom. Topol.**, 13:901–941, 2009.
- [19] M. Hutchings, *Taubes’s proof of the Weinstein conjecture in dimension three*, **Bull. Amer. Math. Soc. (N.S.)**, 47:73–125, 2010.
- [20] D. Ingebreton, *Hausdorff dimension of generic Kuperberg minimal sets*, **Thesis**, University of Illinois at Chicago, 2018.
- [21] D. Ingebreton, *Hausdorff dimension of Kuperberg minimal sets*, preprint, arXiv:1801.04034.
- [22] A. Katok, *Lyapunov exponents, entropy and periodic orbits for diffeomorphisms*, **Inst. Hautes Études Sci. Publ. Math.**, 51:137–173, 1980.
- [23] A. Katok and J.-P. Thouvenot, *Slow entropy type invariants and smooth realization of commuting measure-preserving transformations*, **Ann. Inst. H. Poincaré Probab. Statist.**, 33:323–338, 1997.
- [24] K. Kuperberg and C. Reed, *A rest point free dynamical system on  $\mathbb{R}^3$  with uniformly bounded trajectories*, **Fund. Math.**, 114:229–234, 1981.
- [25] K. Kuperberg and C. Reed, *A dynamical system on  $\mathbb{R}^3$  with uniformly bounded trajectories and no compact trajectories*, **Proc. Amer. Math. Soc.**, 106:1095–1097, 1989.

- [26] K. Kuperberg, W. Kuperberg, P. Minc and C. Reed, *Examples related to Ulam's fixed point problem*, **Topol. Methods Nonlinear Anal.**, 1:173–181, 1993.
- [27] K. Kuperberg, *A smooth counterexample to the Seifert conjecture*, **Ann. of Math. (2)**, 140:723–732, 1994.
- [28] G. Kuperberg and K. Kuperberg, *Generalized counterexamples to the Seifert conjecture*, **Ann. of Math. (2)**, 144:239–268, 1996.
- [29] G. Kuperberg, *A volume-preserving counterexample to the Seifert conjecture*, **Comment. Math. Helv.**, 71:70–97, 1996.
- [30] K. Kuperberg, *Counterexamples to the Seifert conjecture*, in **Proceedings of the International Congress of Mathematicians, Vol. II (Berlin, 1998)**, Doc. Math., Extra Vol. II, 1998, pages 831–840.
- [31] K. Kuperberg, *Aperiodic dynamical systems*, **Notices Amer. Math. Soc.**, 46, no. 9:1035–1040, 1999.
- [32] K. Kuperberg, *personal communication*, November 15, 2021.
- [33] S. Mardešić and J. Segal, **Shape theory: The inverse system approach**, North-Holland Math. Library, Vol. 26, North-Holland Publishing Co., Amsterdam, 1982.
- [34] S. Mardešić, *Absolute neighborhood retracts and shape theory*, in **History of Topology**, pages 241–269, North-Holland Publishing Co., Amsterdam, 1999.
- [35] S. Matsumoto, *Kuperberg's  $C^\infty$  counterexample to the Seifert conjecture*, **Sūgaku**, Mathematical Society of Japan, 47:38–45, 1995. Translation: **Sugaku Expositions**, 11:39–49, 1998, Amer. Math. Soc.
- [36] R.D. Mauldin, **Mathematics from the Scottish Café with selected problems from the new Scottish Book, Including selected papers presented at the Scottish Book Conference held at North Texas University, Denton, TX, May 1979**, Birkhäuser/Springer, Cham, 2015.
- [37] V.S. Medvedev, *A new type of bifurcations on manifolds*, **Mat. Sb. (N.S.)**, 113(155):487–492, 496, 1980.
- [38] J. Palis and C. Pugh, *Fifty problems in dynamical systems*, in **Dynamical systems—Warwick 1974 (Proc. Sympos. Appl. Topology and Dynamical Systems, Univ. Warwick, Coventry, 1973/1974; presented to E. C. Zeeman on his fiftieth birthday)**, Lecture Notes in Math., Vol. 468, pages 345–353, Springer, Berlin, 1975
- [39] D. Peralta Salas, A. Rechtman and F. Torres de Lizaur, *A characterization of 3D steady Euler flows using commuting zero-flux homologies*, **Ergodic Theory Dynam. Systems** 41, no. 7, 2166–2181, 2021.
- [40] P.B. Percell and F.W. Wilson, Jr., *Plugging flows*, **Trans. Amer. Math. Soc.**, 233:93–103, 1977.
- [41] A. Rechtman, *Pièges dans la théorie des feuilletages: exemples et contre-exemples*, **Thèse**, l'Université de Lyon – École Normale Supérieure de Lyon, 2009.
- [42] A. Rechtman, *Existence of periodic orbits for geodesible vector fields on closed 3-manifolds*, **Ergodic Theory Dynam. Systems**, 30:1817–1841, 2010.
- [43] P.A. Schweitzer, *Counterexamples to the Seifert conjecture and opening closed leaves of foliations*, **Ann. of Math. (2)**, 100:386–400, 1974.
- [44] P.A. Schweitzer, *Compact leaves of foliations*, in **Proceedings of the International Congress of Mathematicians (Vancouver, B. C., 1974)**, Vol. 1, 543–546, 1975.
- [45] H. Seifert, *Closed integral curves in 3-space and isotopic two-dimensional deformations*, **Proc. Amer. Math. Soc.**, 1:287–302, 1950.
- [46] A. Shilnikov, L. Shilnikov and D. Turaev, *Blue-sky catastrophe in singularly perturbed systems*, **Mosc. Math. J.**, 5:269–282, 2005.
- [47] L. Siebenmann, *Le paradigme du serpent: explique les contre-exemples de K. Kuperberg à la conjecture de Seifert*, manuscript privée, décembre, 1997.
- [48] C. Taubes, *The Seiberg-Witten equations and the Weinstein conjecture*, **Geom. Topol.**, 11:2117–2202, 2007.
- [49] F.W. Wilson, Jr., *On the minimal sets of non-singular vector fields*, **Ann. of Math. (2)**, 84:529–536, 1966.

STEVEN HURDER, DEPARTMENT OF MATHEMATICS, UNIVERSITY OF ILLINOIS AT CHICAGO, 322 SEO (M/C 249), 851 S. MORGAN STREET, CHICAGO, IL 60607-7045

*Email address:* hurder@uic.edu

ANA RECHTMAN, INSTITUT DE RECHERCHE MATHÉMATIQUE AVANCÉE, UNIVERSITÉ DE STRASBOURG, 7 RUE RENÉ DESCARTES, 67084 STRASBOURG, FRANCE

*Email address:* rechtman@math.unistra.fr